

Lintel Schedule (2021 - Thermally Broken)					
Location	Lintel Ref	Lintel Type	Lintel Bearing - Left	Lintel Bearing - Right	Remarks
Kitchen / Dining	L1	Catnic TS90/100 - 1500 long	126	126	Arched former required to Country Brick variant only
Hall	L2	Catnic TH90/100 - 2250 long	164	164	
Living Room	L3	Catnic TX90/100 - 2250 long	220	220	Rectangular concrete padstone to left side. Rectangular concrete padstone to right side. Arched former required to CB, CT & CW variants only.
Living Room	L4	Catnic TX90/100 - 2700 long	164	164	
Utility	L5	Catnic TS90/100 - 900 long	206	206	
Kitchen / Dining	L6	Catnic TX90/100 - 2700 long	164	164	
Kitchen / Dining	L7	Catnic TS90/100 - 1050 long	183	183	Arched former required to CB, CT & CW variants only.
Kitchen / Dining	L8	Catnic TX90/100 - 2250 long	220	220	Rectangular concrete padstone to left side. Rectangular concrete padstone to right side. Arched former required to Country Brick variant only.
Hall	L9	Catnic BSD100 - 1350 long	205	205	Corrected lintel size to match L10
Store	L10	Catnic BSD100 - 1350 long	205	205	Corrected Bearing width.
Bedroom 1	L11	Catnic TS90/100 - 1200 long	145	145	
Bedroom 1 Ensuite	L12	Catnic TS90/100 - 1200 long	145	145	
Bedroom 3	L13	Catnic TH90/100 - 2250 long	220	220	Arched former required to CB, CT & CW variants only.
Bathroom	L14	Catnic TS90/100 - 1050 long	183	183	
Landing	L15	Catnic TS90/100 - 1050 long	183	183	
Bedroom 2	L16	Catnic TS90/100 - 1650 long	201	201	
Bedroom 2	L17	Catnic TS90/100 - 1050 long	183	183	
Bedroom 1	L18	Catnic TS90/100 - 2250 long	220	220	Arched former required to Country Brick variant only
	L-Elec	Catnic ANG/MBA - 750 long	193	193	Meter Box Lintel
	L-Gas	Catnic ANG/MBA - 750 long	193	193	Meter Box Lintel

Door Schedule - Country Brick											
Door From...	...To	Ref	Structural Height	Structural Width	Door Panel Height	Door Panel Width	Frame	Door Style	Security	Fire	Comments
Hall		D1	2100	1923	2000	907	uPVC Frame, complete with extensions for 20mm check reveal	Country Style GRP Entrance Door	ADQ		Corrected S/O
Hall	Kitchen / Dining	D2	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Utility	Kitchen / Dining	D3	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Cloakroom	Hall	D4	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Hall	Living Room	D5	2033	940	1981	838	Timber (150 x 25)	Internal Vertical Panel Door			
Store	Living Room	D6	2033	940	1981	838	Timber (150 x 25)	Internal Vertical Panel Door		FD30	
Landing	Bedroom 1	D7	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Bedroom 1	Bedroom 1 Ensuite	D8	2033	752	1981	686	Timber (90 x 25)	Internal Vertical Panel Door			
Landing	Bedroom 2	D9	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Landing	Bathroom	D10	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Landing	Bedroom 3	D11	2033	904	1981	838	Timber (90 x 25)	Internal Vertical Panel Door			
Store	Bedroom 3	D12	2033	752	1981	686	Timber (90 x 25)	Internal Vertical Panel Door			

Revision Schedule			
Rev	Date	Description	Drn By
C1	28.11.25	Construction Issue	-

CONSTRUCTION

Bellway

www.bellway.co.uk

Bellway Homes (Eastern Counties)

Building 2030, Cambourne Business Park,
Cambridgeshire CB23 6DW
Tel: 01480 425 200

Project

Somersham
St Ives Road
Working Drawings

Drawing Title		
The Fuller Life		FRL-3B-2S-CB
1053 ft² 3b Det (Corner Turner) Country Brick Lintel & Door Schedules		
Drawing Created By	First Issue Date	Scale(s)
Group	April '25	
Project No	Drg Status	Revision
BI01	Construction	C1
Drawing No.		BI01/1053FRL/90/CB/01